

**WATERLINE FLUSHING AFTER CONSTRUCTION / SYSTEM DISINFECTION**  
**WITH DISCHARGE HAUL OFF**  
**(USED FOR DUST CONTROL / COMPACTION)**

1. PREPARATION

- a. Determine chlorine content of discharged water.
- b. Determine appropriate construction activity for treatment.

2. PROCESS

- a. Flush to tanker for disposal on unpaved construction activity for dust control or compaction.
- b. Conform that application of water is in appropriate location.

3. ACTIONS

- a. Remove equipment from flush point.

4. DOCUMENTATION

- a. Residual test of discharged water.
- b. Location of water discharged.